

# Installation of changeover switches for dipole and quadrupole magnet on a new beam transport line

K. Kumagai <sup>\*1</sup> and N. Fukunishi <sup>\*1</sup>

A new beam transport line dedicated to provide high-energy beams for biological experiments was constructed in the last year<sup>1),2)</sup>. Beam commissioning of the beam line was carried out from January 24<sup>th</sup> to 25<sup>th</sup> in 2015. A 160MeV/u <sup>40</sup>Ar beam was transported from a beam exiting point of IRC to the confluent point connected to the existing beam line within 30 min. After the beam commissioning succeeded, an Ar beam was transported to the E5 experimental vault and beam irradiation to seaweed samples was carried out promptly.

One-third of dipole magnets and two-thirds of quadrupole magnets on the new beam transport line were operated with existing power supplies by switching or changing the polarity of the magnet. At the time of commissioning, the switching of the magnets and/or their polarity was performed manually. The switching of all magnets took several hours. Because it was assumed that the frequency in use of the beam line becomes larger by having succeeded in the beam commissioning, we decided to install power source changeover switches to switch magnets and/or their polarity automatically using buttons.

Table 1 summarizes the scheme of the switching for the dipole magnets and Table 2 shows that for the quadrupole magnets. The automatic transfer switch type SSK-C produced by KYORITSU KEIKI CO., LTD. was used to switch dipole magnets, and type SSK-E was used to switch quadrupole magnets. Both switches have the functions of instantaneous excitation and mechanical holding. In the case of quadrupole magnets, two families of circuits can be switched using one switch. In the case of resistive load, these switches were designed such that switching was possible in the state in which an electric direct current spread in, but the inductance of the magnet might damage the contacts of switches. We designed the switches such that they are not able to switch when an electric current flows. In addition, they were not able to switch when the current sensing device broke down. An electric current passing through the circuit was detected by the current sensing device using a shunt resistor. It is designed such that a switch becomes effective when the electric current is less than approximately 1.6 mA for a dipole magnet and 3

Table 1. Scheme of switching for dipole magnets.

Channel	Power supply	Specification	New beam line	IRC bypass beam line
1	BT_D10_4	330A-60V	DMR3	⇔ DMK9 <sup>a)</sup>
2	BT_D10_3	330A-85V	DMR4	⇔ DMH8 <sup>a)</sup>
3	BT_D8_2	330A-155V	DMR5	⇔ DMH7 <sup>a)</sup>

<sup>a)</sup> Polarity Change

<sup>\*1</sup> RIKEN Nishina Center

mA for a quadrupole magnet.

The interlock signals of overheat and the coolant stop of both magnets are equipped in the power supply, but the signals originating from a magnet that is not connected are unnecessary. Therefore, the interlock was designed to be masked using the auxiliary contacts of the switching device.

Table 2. Scheme of switching for quadrupole magnets.

Channel	Power supply	New beam line	Injection beam line to SRC	IRC bypass beam line
1	BT_QB4_1	QDR63a	⇔	QDG21a
	BT_QB4_2	QDR63b		QDG21b
2	BT_QB4_4	QDR64a	⇔	QSG23
	BT_QB4_5	QDR64b		QSG24
3	BT_QA5_1	QTR72b	⇔	QDG26a
	BT_QA5_2	QTR72c		QDG26b
4	BT_QA5_3	QDR71a	⇔	QDG41a
	BT_QA5_4	QDR71b		QDG41b
5	BT_QA5_5	QSR73	⇔	QDG51a
	BT_QA5_6	QSR74		QDG51b
6	BT_QB4_6	QTR72a	⇔	QSG25
7	BT_QB1_1 <sup>c)</sup>	QDR31c	⇔	QTH81a <sup>a)</sup>
	BT_QB1_2 <sup>c)</sup>	QDR31b		QTH81b <sup>a)</sup>
8	BT_QB1_3 <sup>c)</sup>	QDR31a	⇔	QTH81c <sup>a)</sup>
9	BT_QB5_1		QSH17 <sup>b)</sup>	⇔ QSH61
10	BT_QC2_2	QDR61a	⇔	QDG11a
	BT_QC2_3	QDR61b		QDG11b
11	BT_QC2_4	QDR62a	⇔	QDG12a
	BT_QC2_5	QDR62b		QDG12b
12	BT_QC1_2	QDR01a	⇔	QDK02a
	BT_QC2_1	QDR01b		QDK02b
13	BT_QA6_5 <sup>c)</sup>	QSR11	⇔	QTG92b

<sup>a)</sup> Polarity Change

<sup>b)</sup> On the injection beamline to IRC

<sup>c)</sup> Specification of these power supplies is 150A-40V and that of the rest of the power supplies is 150A-30V.

The switches were manufactured from June to August. In September, installation, wiring and a check of wiring and magnet polarity were carried out. The first irradiation after installing the switches was carried out from 5<sup>th</sup> to 7<sup>th</sup> October and was finished satisfactorily. The next irradiation is scheduled for 27<sup>th</sup> to 29<sup>th</sup> January, 2016.

## References

- 1) K. Kumagai et al., RIKEN Accel. Prog. Rep. 48, 189 (2015).
- 2) Y. Watanabe et al., RIKEN Accel. Prog. Rep. 48, 19 (2015).